

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

Lead for Disposal of Debris shall be payable at cartage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work.

MODIFIED DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Byatarayanapura Division
BBMP, Bangalore - 92

Name of the Work : Improvements to roads and Drains at Byrappa Garden in Ward No. 10 Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	56.40	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	90.72	
2	100.80	KSRRB M300-53: Construction of embankment with approved material gravel/murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murum, watering charges & compaction by vibratory roller)	Cum	163.24	
3	75.60	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum and fine aggregates @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth , including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4290.84	
4	50.40	KSRRB M2600-3: Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification	M	137.16	
5	75.60	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	Cum	6464.88	
6	504.00	Vaccum De-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift	Sqm	91.80	


Sl. No.	Quantity	Description	Unit	Rates	
				In Figures	In Words
7	56.40	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	72.71	



Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಇದರ ಬೆಂಚರ್ ಪಡೆಯಲು
ಬಿಟ್ಟುಕೊಡಲಾಗಿದೆ ಸಂಖ್ಯೆ.....()
ಬಿಟ್ಟುಕೊಡಲಾಗಿದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ

DTS approved


Superintending Engineer
Yelahanka Zone
BBMP, Bangalore - 92

8E

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92

BBMP, Bangalore - 92